Team-III

Establishment of Green House

Climate Control Green House (13.433 Sqfts) was established near the Department of Biosciences and Sericulture which was partitioned into six chambers, where exhausters and cooling pads are placed. To maintain humidity, a humidifier/mystifier was also placed. All these chambers are facilitated with water.

Greenhouse Measurement

Total sqmts	Total Sqfts	Each chamber in sqmts
1248 sqmts i.e. 48mtsx26mts	13433 sqfts i.e. 1sqmt=10.76sqft 10.76x1248 =13433sqft	208 sqmts i.e. 8mtsx 26mts

Green House



